4. Each tender must be accompanied by a deposit of Rs. 500 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing Bangalore Power and Light Work Shop and Stores" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Secretary to Government, Public Works Department who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Chief Electrical Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract estimate for additions and alterations to Bangalore Power and Lighting Stores and constructing a new work shop for Bangalore Power and Lighting at Bangalore.

No.	Items of work	Per	Quantity
1	Dismantling corrugated iron roofing, purlines, etc.	Sql	80·89
2	Earthwork excavation and filling in basement	C. yd.	192
3	Concrete foundation	C. ft.	1,820
4	Stone in mortar, foundation and basement	"	3,652
5	Brick in mortar superstructure	"	10,428
6	Stone slabs 6" thick dressed	Sq. ft.	236
7	Brick in mortar arch work, with centrings	C. ft.	4,387
8	Plastering with mortar	Sq.	173·5
9	White and color washing	"	173·5
10	Cuddappah slabs (1½") flooring over 3" chunam concrete, cement painting, etc., complete.	"	24·22
11	Gravel flooring 9" thick	"	29·07
12	Galzd. corrugated iron roofing	"	118·14
13	Galzd. iron sheeting to valleys	L. ft.	116
14	Second hand meter gauge rails with fish plates	No.	88
15	Teakwood work with wood oiling	C. ft.	75·75
16	W. iron trusses 31½ feet clear span	No.	1
17	Do 30 do	"	4
18	Hoisting carriage charges for trusses	"	5
19	Teakwood ornamental eaveboarding (9"×1")	R. ft.	639
20	Teakwood panelled doors 1¾"×2" thick	S. ft.	279
21	Teakwood glazed windows with iron bars	"	415
22	Teakwood glazed cir. ventilators	"	45
23	Painting with 3 coats of silicate painting	Sq.	44·2

S. G. FORBES,
Chief Electrical Engineer to the Government of Mysore.

SANITARY DIVISION.

Notice is hereby given that quotations will be received in the office of the Executive Engineer, Sanitary Division, up to 4 P.M., on 28th July 1918, for supplying the following furniture within a month of the acceptance of the quotations. The successful competitor will be required to deliver the furniture at this office premises.

Items	Per	Quantity
Drawing and Officers' tables with two drawers (5′×3′×2½′)	Each.	3
Chairs, rosewood, with arm, rattan bottom and back	"	5
Almirahs, teakwood (6′×3½′×1½′)	"	2
Stools, teakwood	"	6
Record boxes, teakwood (3′×2′×2½′)	"	5
Calling bells	"	2
Clocks	"	2
Alighar locks of 2½", with duplicate keys	"	10
Rattan trays	"	5

Dated 9th July 1918.

It is hereby notified that a sum of Rs. 144-15-6, being the amount due to contractor Mr. N. Ramiah for diverting Storm Water Drain in Basavangudi Extension, is outstanding in the books of this office. If the same is not claimed by the party or claimant within three months from this date, the amount will be credited to Government.

Dated 20th July 1918.

Notice is hereby given that quotations will be received in the office of the Executive Engineer, Sanitary Division, up to 4 P.M., on 10th August 1918, for supplying the following drawing materials within fifteen days of the acceptance of the quotations, the successful competitor to deliver the drawing materials at this office premises. The outside competitors may deliver the same F. O. R., Bangalore City:—

Items	Per	Quantity.
Mathematical instrument 1st class in box complete. (P. Orr & Sons, Madras and Rangoon Paris make)	Set	2
Mathematical instrument 3rd class in box complete. (P. Orr & Sons, Madras and Rangoon Paris make)	"	4
Drawing board double elephant	No.	1
Saucers for mixing colours containing 6 in Nos.	"	2
Brass parallel ruler 12"	"	2
T.-squares wooden 36" vulcanite edge ...	"	2
Vulcanite set squares 6" of 45° (Winson and Newton) ...	"	2
Do 6" of 60° do ...	"	2
Wooden plotting scales six in Nos. in box with offsets (Winson and Newton)	"	3
Planimeter in box complete (Maker P. Orr & Sons) ...	"	1

N. SUBBA RAO,
Executive Engineer.

BANGALORE DIVISION.

Abstract Notification.

Attention is invited to the notification published in Part IV of the *Mysore Gazette*, dated the 11th July 1918, calling for tenders for the purchase of burnt stone slabs at Silledar Lines, Bangalore.

C. VIJAYARANGAM NAIDU,
Executive Engineer.

TUMKUR DIVISION.

Dated 13th July 1918.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Tumkur Division, up to 5th August 1918, for constructing 7 blocks of 5 huts each for Barr Sepoys at Tumkur. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1920.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Tumkur between the hours of 11 A.M. to 5 P.M., except Sundays and Government holidays.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 1,500, in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing 7 blocks of 5 huts each for Barr Sepoys at Tumkur," in default of which tenders will be rejected.